

NOTES:

- BEDDING SHALL BE THE FULL WIDTH OF THE TRENCH WHERE SHORING AND BRACING IS REQUIRED.
- 2. ALL BACKFILL SHALL BE FREE AND CLEAR OF STONES GREATER THAN 2".
- 3. ALL BACKFILL MATERIAL SHALL BE SUITABLE, NATIVE MATERIAL APPROVED BY CITY OF BURLINGTON.
- 4. BACKFILL SHALL BE PLACED AND COMPACTED IN 6" LIFTS.
- DEFLECTION TESTING SHALL TAKE PLACE 30 DAYS AFTER BACKFILL OPERATIONS ARE COMPLETE. IN LIEU OF WAITING 30 DAYS, COMPACTIONS TESTING MAY BE COMPLETED SHOWING 95% TRENCH COMPACTION.
- 6. UNSUITABLE TRENCH BOTTOM MATERIAL SHALL BE REPLACED WITH FOUNDATION MATERIAL TO THE SATISFACTION OF THE CITY ENGINEER.
- 7. INITIAL BACKFILL SHALL BE HAND WORKED AND TAMPED.



DATE	REVISED	SCALE	DETAIL	$CC \cap C$
07/01/20		NOT TO SCALE		55-2